

BANGALORE DISTRICT.

NOTIFICATION.

The 24th April 1893.

The following articles of Minor Forest produce will be excluded from annual sales alluded to in this Office Notification of 11th May 1892, published in the Mysore Gazette of 2nd June 1892.

- | | |
|------------------|--------------------|
| 1. Lac. | 3. Kakke bark. |
| 2. Toppala bark. | 4. Poppali chakke. |

S. VAIDYANATHA IYER,
for Dy. Commr.

TUMKUR DIVISION.

ADVERTISEMENT.

The —th May 1892.

Tenders are hereby invited for restoring Kitnagamaangala Tank, Registered No. 6, Kunigal Taluk, Tumkur District.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's Office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 26th May 1893.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 200 as earnest money.

6. Within 8 days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

Detailed Abstract.

| Items of Work. | Per. | Quantity. | Rate. | Cost. |
|---|-----------|-----------|-------|---------|
| <i>Bund—</i> | | | | |
| Earthwork | C. Yd. | 37,011 | | |
| Excavation to puddle wall | Do | 560 | | |
| Earthwork filling puddle | Do | 560 | | |
| Old stone work | Do | 3,940 | | |
| New stone work | Do | 2,320 | | |
| B. M. stones | No. | 2 | | |
| Grade stones including index and bed slabs | Do | 37 | | |
| Gauge stone | Do | 1 | | |
| Registered No. stone | Do | 1 | | |
| <i>Sluice—</i> | | | | |
| Rebuilding sluice | Lump Sum. | | Rs. | 250 0 0 |
| Waste weir Right 250 feet long brick in chunam | C. Ft. | 3,268 | | |
| Stone slabs nicely dressed | S. Ft. | 394 | | |
| Chunam plastering | Sqrs. | 6.81 | | |
| Rough stone from kodi | C. Yd. | 564 | | |
| Clearing approaches and lowering the abandoned kodi | Lump Sum. | | Rs. | 150 0 0 |

C. T. DALAL,
Executive Engineer.